

Bond 2018

CALLICOATTE ROAD (18010A)

IH-37 to Up River Road

Project Fact Sheet



PROJECT DESCRIPTION:

Scope: The construction will include new concrete pavement, driveways, pavement markings, signage, street lighting improvements, storm water drainage improvements, potable water improvements (domestic water distribution and fire protection), wastewater improvements, and gas line improvements.

PROJECT FACTS

Project Consultant Engineer: Munoz Engineering, LLC.

City Project Manager: Larry Wenger

Contractor: Reytec Construction Resources, Inc.

Construction Inspector: Oscar Nesmith

Anticipated Award Date: October 19, 2021

Anticipated Construction Start: January 2022

Anticipated Completion: November 2022

Total Project Value: \$1,927,197.50

Additional Notes/Details:

In addition to the new roadway the following scope of work will be completed:

- Street Lighting Improvement include the following:
Installation of three new mast arms with Cobra Head LED lights.
- Storm Water improvement include the following:
Installation of underground storm infrastructure including storm water lines, laterals, grate inlets and drainage swales in order to improve drainage flow towards Up River Road.
- Water improvements include the following:
Installation of 6" C900 waterline extension from Rehfeld Road along the northside of the access road to Callicoatte Road, and the installation of an 8" C900 PVC waterline along the Northside of Callicoatte Road down to Up River Road as well as the required fire hydrants.
- Wastewater improvements include the following:
Installation of 8" wastewater line and wastewater manholes along the southside of Callicoatte Road